## Roadway Rendering



#### **Phase 1 of Construction**

#### Phase 1 Construction: Two-Way Access Road

400' – 600' Right of Way

RESERVED

FOR

FUTURE

Phase 1 would consist of a single roadway with one eastbound and one westbound travel lane.

### **Phase 2 of Construction**

# Potential Phased Construction Option: One-Way Access Roads

400' – 600' Right of Way

RESERVED

FOR

FUTURE

Phase 2 would be constructed as traffic warrants and funding becomes available.

- The new location Loop 9 frontage road system would include an eastbound and westbound frontage road facility, each consisting of three 12-foot lanes, an 8-foot inside shoulder, and an 8-foot outside shoulder.
- The proposed project ROW would include a median wide enough to accommodate the future construction of an ultimate access-controlled mainlane facility.

